


The *Lynx* Mission Concept Revealing the Invisible Universe


Douglas A. Swartz (Deputy Study Scientist, MSFC)

-Presented On behalf of the *Lynx* Team



X - R A Y O B S E R V A T O R Y

LYNX



Meet *Lynx*!



One of 4 large missions under study for the 2020 Astrophysics Decadal, Lynx is an X-ray observatory that will directly observe the dawn of supermassive black holes, reveal the invisible drivers of galaxy and structure formation, and trace the energetic side of stellar evolution and stellar ecosystems.

Lynx will contribute to nearly every area of astrophysics and provide synergistic observations with future-generation ground-based and space-based observatories, including gravitational wave detectors.

Lynx will provide unprecedented X-ray vision into the “Invisible” Universe with leaps in capability over *Chandra* and *ATHENA*:

- 50–100× gain in sensitivity via high throughput with high angular resolution
- 16× field of view for arcsecond or better imaging
- 10–20× higher spectral resolution for point-like and extended sources





THE SCIENCE

Lynx is designed to pursue three science pillars.

There are ample resources for many other programs, including those unexpected today.

It will be a discovery platform for all.

WWW.HIDDENCOSMOS.ORG




DAWN OF BLACK HOLES



DRIVERS OF
GALAXY EVOLUTION



THE ENERGETIC SIDE OF
STELLAR EVOLUTION

The header image features a dark space background with a purple nebula on the right. On the left, there is a stylized illustration of the Lynx X-ray telescope with its two large mirrors and a cat's face superimposed over it.

Lynx Study Office & STDT Activities

- Lynx Mirror Architecture Trade (LMAT) 01/2018 – 07/2018
 - recommend baseline optics design
 - adopted by STDT – 08/2018
- Large Mission Concept Studies Report Team (LRT) 05/2018 – 06/2018
- Lynx “science” website launched ~07/2018
 - <https://www.hiddencosmos.org>
- Interim Report submitted 08/2018
 - <https://wwwastro.msfc.nasa.gov/lynx/docs/LynxInterimReport.pdf>
- X-ray Grating Spectrometer architecture trade – 08/2018
- Mission Design Lab (at GSFC) – 09/2018
 - system-level independent assessment
- Second Architecture Design Study – 08/2018 – ongoing
 - requested by NASA to provide a less costly option and a range of scientific scope – 06/2018
- Special Section Journal of Astronomical Telescopes, Instruments, and Systems (JATIS) 10/2018 – 03/2019
- Large Mission Concept Independent Assessment Team (LCIT) – ongoing
 - a cost & technical credibility analysis & validation of the technical, cost, and schedule requirements defined by the Lynx study
- Science White Papers submitted to Decadal Survey – 03/2019

Decadal Deliverables Schedule

X-RAY OBSERVATORY


LYNX



Study Deliverables

M1	Comments on Study Requirements and Deliverables – Accept the study requirements/deliverables and submit plan—or – Provide rationale for modifying requirements/deliverables	April 29, 2016
O1	Optional: Initial Technology Gap Assessment – To impact PCOS/COR/ExEP 2016 technology cycle	June 30, 2016
O2	Optional: Update Technology Gap Assessments	June 2017
M4a	Interim Report March 2018 – Provide science case and mission concept (use CML 3 as a guide) – Deliver initial technology roadmaps; estimate technology development cost/schedule – CML 4 tailored approach (optional)	
O3	Update Technology Gap Assessments	June 2018
M4b	Update Interim report with LRT comments incorporated (Public Release)	August 15, 2018
M6a	Required Input Data released by STDts to HQ – Support independent cost estimation/validation process – HQ submits to Large mission studies Cost Assessment Team (slide 35)	April 26, 2019
M6b	LCIT reconciliation with STDts	July 2019
M7	STDts Final Reports delivered to HQ – As described in study success criteria chart 15	August 23, 2019
M8	HQ Submits final report to Decadal	September 2019

Lynx Study Look Ahead




Lynx Study Look Ahead


Task	July 2019					August 2019				September 2019				
	1	8	15	22	29	5	12	19	26	2	9	16	23	30
LCIT / HQ Milestones	7/5 (TBD)				8/5 (TBD)			8/23		9/30 (TBD)				
	LCIT Feedback to STDts				LCIT Report to HQ			STDt Reports to HQ		Deliver Reports to Decadal				
Conferences						8/13-8/15 8/15 (TBD)								
						SPIE CxC Workshop								
Science and Tech Team Activities	Tech. Development													
Tech Roadmap Development	Roadmap Updates as Needed													
ACO Analysis	None planned													
Cost Analysis	None planned													
Final Report Development	7/5 (TBD)				8/1 – 8/8 (TBD)			8/23						
	LCIT Comments				MSFC Mgmt Briefings			Deliver to HQ						

Decadal decision anticipated ~December 2020



Proven Observatory Architecture








High-Definition X-ray Imager

Ralph Kraft, SAO

Abe Falcone, Penn State University

Mark Bautz, MIT




- Initial instrument design developed by MSFC Advanced Concepts Office (ACO)
- Fully samples Lynx 22'x22' sub-arcsecond FOV
- >100 frames/s in full frame mode (10^4 in 20px20p window mode); >8000 c/s full field event rate






HDXI: Multiple Sensor Approaches

- Monolithic CMOS Active Pixel Sensor
 - Single Si wafer used for both photon detection and read out electronics
 - SRI/SAO (and MPE)
- Hybrid CMOS Active Pixel Sensor
 - Multiple bonded layers, with detection layer optimized for photon detection and readout circuitry layer optimized independently
 - Teledyne/PSU
- Digital CCD with CMOS readout
 - CCD Si sensor with multiple parallel readout ports and digitization on-chip
 - LL/MIT





Lynx X-ray Microcalorimeter

Main Array

- 1" pixels, 5' FOV, 50 μm pixels
- ~ 3 eV, 10 cps/hydra (5")
- Up to 7 keV
- 86.4 kpix

Enhanced Main Array




- 0.5" pixels, 1' FOV, 25 μm pixels
- 1.5 eV, 20 cps/hydra (2.5")
- Up to 7 keV
- 12.8 kpix

Simon Bandler


NASA/Goddard Space Flight Center

Ultra-High-Res Array

- 1" pixels, 1' FOV, 50 μm pixels
- 0.3-0.4 eV (up to ~ 0.75 keV)
- Count rate ~ 80 cps/1" (single pixel)
- 3.6 kpix



Space Nanotechnology Lab
MIT Kavli Institute for
Astrophysics and Space Research



X-ray Mirror Assembly

Will Zhang

NASA/Goddard Space Flight Center



Silicon Meta-shell Optics

Focal Length:	10 m
Outer Diameter:	3 m

Effective Area	
1 keV	$>2 \text{ m}^2$
6 keV	0.2 m^2


On-Axis HPD:	0.5"
FOV w/ 1" HPD:	10'




Direct-fabrication Mirror Segments




1. Mono-crystalline silicon block




2. Conical form generated




3. Light-weighted substrate



4. Etched substrate




5. Polished mirror substrate




6. Trimmed mirror substrate




The Process of Building a Mirror Module




1. Silicon plate with small silicon spacers that are precisely ground to prescribed radial heights.



2. Mirror segments are placed on spacers, settled by vibrations. The baffle is shown for completeness and has no precision to speak of.



3. Once epoxy cures, another set of spacers are attached to repeat the process for the next layer of mirror segments.




Flight Plate



Interim Plate


4. The previous steps repeat until a full mirror module is completed. The interim silicon plate is removed at the end of the buildup process.



Steps in Lynx Mirror Assembly Build

37,492


Segments



~0.01 kg ea.

611


Modules



~1.5 kg ea.

12


Meta-shells



~80 kg ea.

1

Assembly




~1,000 kg



Process Validated by X-ray Testing


Full Illumination X-ray Measurement at GSFC and MPE Panter



**Effective Area at 4.5
keV (cm²)**

0.266 predicted

0.260 measured



**Image at 4.5 keV: 2.2" HPD
(logarithmic color scale)
approaches TRL 4**